
#### **VICINITY MAP**



#### SHEET INDEX

#### SHEET DESCRIPTION

- 1 VICNITY MAP AND SHEET INDEX
- 2 LEGEND AND ABBREVIATIONS
- 3 ACCESS AND TRAFFIC CONTROL
- 4 EXISTING CONDITIONS AND SURVEY CONTROL
- 5 CLEARING-REMOVALS AND TESC
- 6 TESC DETAILS AND NOTES
- 7 PROPOSED DESIGN PLAN VIEW
- 8 PROPOSED DESIGN SECTION VIEW
- 9 PROPOSED DESIGN SECTION VIEW 2
- 10 ENGINEERED LOG JAM PLAN AND SECTION
- 11 ENGINEERED LOG JAM SEQUENCE
- 12 ENGINEERED LOG JAM DETAILS AND NOTES
- 13 PLANTING PLAN
- 14 PLANTING PLAN DETAILS

# **BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4** WRIA 8

LAT 47.448 LONG -122.074

KING COUNTY RIVER AND FLOODPLAIN MANAGEMENT KING STREET CENTER
201 S JACKSION ST SUITE 5600 SEATTLE, WA 98104-3855

PROJECT MANAGER: LINDA BARTOLINI VENEGAS PHONE: (206) 263-9022 EMAIL: LBARTOLI@KINGCOUNTY.GOV

PROJECT ECOLOGIST: ALEX LINCOLN PHONE: (206) 263-0989 EMAIL: ALINCÓLN@KINGCOUNTY.GOV

PROJECT ENGINEER: MARK BEGGS, P.E. PHONE: (206) 773-3702 EMAIL: MBEGGS@KINGCOUNTY.GOV

#### OWNER CONTACT INFORMATION: LEGAL AND SURVEY DESCRIPTION:

THE PROJECT LIMITS ARE WITHIN UNINCORPORATED KING

THIS PROJECT SITE IS WITHIN A PORTION OF THE SW, SECTION 29, T23N., R06E., W.M.

ZONED: RA-10

PARCEL: 292306-9021

LEGAL DESCRIPTION: C P S R/W ACROSS W 1/2 OF SEC

PARCEL: 292306-9035

LEGAL DESCRIPTION: POR GL 8 & 10 LY ELY OF C & P S R/W & NLY OF LN BEG AT PT ON ELY MGN C & P S R/W 550 FT N OF S LN OF GL 8 TH S 05-17-00 E 30 FT TH N 73-27-09 E 683 FT M/L TO RIVER W 20 FT FOR RD LESS C/M RGTS



Know what's below. Call before you dig. (UNDERGROUND UTILITY LOCATIONS ARE APPROX

		INCIN.	KEVISION	101	DAIL	
			-OCN			] ^
FIELD BOOK: DS/BM	05/2021		DESIGN			l,
			30% 0			١'n
SURVEYED: DS/BM	05/2021		DRAFI			] "
CURVEY PAGE MAD CTU	05/2021		DITA			Jε
SURVEY BASE MAP: <u>STH</u>	05/2021		-210022			1
CHECKED: KLA	05/2021		0/12022			] D
CHECKED: KLA	03/2021		<b>V</b> ·			1
		NUM.	RECORD CHANGES APPROVED	BY	DATE	]
						1
						10

	APPROVED: MARK RUEBEL, P.E.	07/2022	
	AFFROVED.	<u> </u>	
	PROJECT MANAGER: LINDA BARTOLINI VENEGAS	07/2022	
		07 /0000	
	ECOLOGIST: ALEX LINCOLN	07/2022	PK
	DESIGNER: MARK BEGGS, P.E.	07/2022	co
		/	
	DARIAN KIS-YOUNG, E.I.T.	07/2022	
	<u>-</u>	07/2022	
_	CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.	07/2022	
	0/10 020/01/12		

1139129





Department of Natural Resources and Parks Water and Land Resources Division River and Floodplain Christie True, Director

**BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4** 

**VICNITY MAP AND SHEET INDEX** NOT FOR CONSTRUCTION

SHEET 1 OF 14 **SHEETS** 

#### **GENERAL NOTES:**

- 1. BEFORE BEGINNING CONSTRUCTION VERIFY THAT EXISTING SITE CONDITIONS ARE AS INDICATED IN THE DRAWINGS AND SPECIFICATIONS. RIVER CHANNEL BANK TOPOGRAPHY WAS SURVEYED IN MAY 2021, AND WILL LIKELY HAVE CHANGED BY TIME OF CONSTRUCTION.
- 2. ALL LOCATIONS OF EXISTING UTILITIES SHOWN HEREIN HAVE BEEN ESTABLISHED BY FIELD SURVEY OR OBTAINED FROM AVAILABLE RECORDS AND SHOULD THEREFORE BE CONSIDERED APPROXIMATE ONLY AND NOT NECESSARILY COMPLETE. INDEPENDENTLY VERIFY THE ACCURACY OF ALL UTILITY LOCATIONS SHOWN AND FURTHER DISCOVER AND AVOID ANY OTHER UTILITIES NOT SHOWN HEREON WHICH MAY BE AFFECTED BY THE IMPLEMENTATION OF THIS PLAN. IMMEDIATELY CONTACT THE PROJECT REPRESENTATIVE IF A UTILITY OR OTHER EXISTING CONDITION PRESENTS A CONFLICT OR OTHERWISE PREVENTS OR INTERFERES WITH COMPLETION OF THE WORK.
- 3. LOCATE AND PROTECT NEARBY EXISTING UTILITIES, STRUCTURES, PAVEMENTS, AND FACILITIES WHICH ARE NOT ABANDONED OR REMOVED DURING CONSTRUCTION.
- 4. TRAFFIC CONTROLS SHOWN ON SHEET 3 ARE THE MINIMUM REQUIRED AND SHALL BE AUGMENTED BY THE CONTRACTOR IN ACCORDANCE WITH CONTRACTOR'S TRAFFIC CONTROL PLAN (TCP). CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL PLAN PER MUTCD AND SPECIFICATIONS.
- THE CONTRACTOR SHALL STAKE THE PROJECT CONSTRUCTION LIMITS FOR APPROVAL BY THE PROJECT REPRESENTATIVE AT LEAST 5 WORKING DAYS PRIOR TO COMMENCING ONSITE ACTIVITIES. ALL CLEARING NECESSARY FOR CONSTRUCTION SHALL BE LIMITED TO THE AREA REQUIRED FOR SAFE EQUIPMENT OPERATION AND TO MINIMIZE THE AREA OF DISTURBANCE. CLEARING LIMITS SHALL NOT BE EXPANDED UNLESS APPROVED BY THE PROJECT REPRESENTATIVE. THE CONTRACTOR SHALL PRESERVE AS MUCH EXISTING VEGETATION AS POSSIBLE AND NOT DAMAGE OR DISTURB VEGETATION MARKED BY THE PROJECT REPRESENTATIVE FOR PRESERVATION.
- 6. A COPY OF THE CONTRACT DRAWINGS, SPECIFICATIONS, AND ANY REQUIRED PERMITS MUST BE ON SITE AT ALL TIMES DURING CONSTRUCTION.
- TREES AND BRUSH NOT SHOWN ON THE PLANS MAY BE ENCOUNTERED DURING CONSTRUCTION ACTIVITIES, THE PROJECT REPRESENTATIVE SHALL IDENTIFY AND FLAG ALL TREES TO BE REMOVED PRIOR TO CONSTRUCTION IN THE PROJECT AREA
- 8. PERFORM ALL CONSTRUCTION IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE, COUNTY, AND CITY PERMIT REQUIREMENTS
- ALL EQUIPMENT OPERATING IN AREAS OTHER THAN THE EXISTING ROAD AND GRAVEL SHOULDER SHALL USE ONLY BIODEGRADABLE VEGETABLE BASED HYDRAULIC FLUIDS OR APPROVED OTHER.

#### SOURCES OF INFORMATION:

LIDAR

KING COUNTY 2021

AERIAL IMAGERY

KING COUNTY 2021

ORDINARY HIGH WATER

KING COUNTY ECOLOGIST AUG 2021

#### TOPOGRAPHIC AND BATHYMETRIC SURVEY

**PARAMETRIX** TOPOGRAPHIC SURVEY MAY 2021 BATHYMETRIC SURVEY MAY 2021

HORIZONTAL DATUM THE HORIZONTAL DATUM FOR THIS SURVEY IS NAD 83/11 WASHINGTON STATE PLANE COORDINATE SYSTEM, NORTH ZONE BASED ON GPS FIELD SURVEY TO WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT) MONUMENT DESIGNATIONS GP17169-353 AND IS17243. POINT DEŚIGNATION GP17169-353 NORTHING: 169,561.990 EASTING: 1,332,190.262 POINT DESIGNATION IS17243 NORTHING: 169,347.394 EASTING: 1,332,159.209

THE VERTICAL DATUM FOR THIS SURVEY IS NAVD 88 BASED ON GPS FIELD SURVEY TO WSDOT MONUMENT DESIGNATION GP17169-353. FIFVATION = 225.872


#### **EXISTING LINE TYPES:**

425	MAJOR 5' CONTOUR (EXISTING)
422———	MINOR 1' CONTOUR (EXISTING)
	PROPERTY LINES
R/W	RIGHT-OF-WAY
	EDGE OF ASPHALT/ PAVEMENT
	EDGE OF WATER (DATE)
	ORDINARY HIGH WATER
	EXISTING RIP-RAP
	PAINTED ROAD LINES
	EDGE OF VEGETATED AREA
	SURVEY LIMIT LINE
	LOW WATER LINE
	DAMAGED AREA
	100 YR FIS EL.
	EXISTING GROUND
	TEMPORARY PUMP/BYPASS LINE
	WETLAND BOUNDARY
	INTERSTATE FIBER OPTIC LINE

#### **DESIGN LINETYPES:**

10	MAJOR 5' CONTOUR
12	MINOR 1' CONTOUR
	CLEAR AND GRUB LINE
	TURBIDITY CURTAIN
	BULK BAG COFFER DAM
	BYPASS
-	STRAW WATTLE
	PROJECT LIMITS
	SILT FENCE
	BULK BAG ISOLATION

## DRAWING REFERENCE:





ROJECT No.

ONTRACT

1139129

#### LEGEND:

# CP #10006

POWER POLE WITH ANCHOR

EXISTING DECIDUOUS TREE

**EXISTING CONIFEROUS TREE** 

SURVEY CONTROL POINT

STABILIZED CONSTRUCTION ENTRANCE CORRUGATED STEEL PLATE CONSTRUCTION ENTRANCE STAGING/STOCKPILE AREA

REMOVE EXISTING TREE

COIR BLANKET

COIR LIFTS

SLASH AND RACKING EXISTING REVETMENT

SELECT FILL FILTER LAYER

CLASS C ROCK

EXISTING BANK MATERIAL

NATIVE PLANTINGS

SIGNAGE

**ACCESS** 

TREE REMOVAL NUMBER

SB-X

XXXX

2010 BORING LOCATION

WATER INFILTRATION AREA

PARCEL NUMBER (2923069-XXXX)

#### **ABBREVIATIONS:**

KC

MUTCD

**APPROXIMATELY** COMP COMPACTED CONTROL POINT CRUSHED SURFACING BASE COURSE CSRC DIAMETER AT BREAST HEIGHT DBH DIAMETER DIA **ELEVATION** ENGINEERED LOG JAM FXIST **EXISTING** FLOOD INSURANCE STUDY FIS FT FEET/FOOT

INVERT ELEVATION KING COUNTY KC WLRD KING COUNTY WATER AND LAND RESOURCES DIVISION MINIMIIM

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES

NORTH NTS NOT TO SCALE ORDINARY HIGH WATER OHW **PMX** PARAMETRIX

QUANTITY RCKC REBAR AND CAP, KING COUNTY RD ROAD

R/W RIGHT-OF-WAY SOUTHEAST SF SQUARE FEET/FOOT SPECS **SPECIFICATIONS** SOLIARE SQ ST STREET STA STATION

TRAFFIC CONTROL PLAN **TESC** TEMPORARY EROSION AND SEDIMENT CONTROL **TEMPORARY** 

TEMP TYPICAL TYP YEAR AND

Know what's below. Call before you dig. (UNDERGROUND UTILITY LOCATIONS ARE APPROX

30% DESIGN FIELD BOOK: DS/BM 05/202 DRAFT SURVEYED: DS/BM 05/202 07/2022 SURVEY BASE MAP: STH 05/202 CHECKED: KLA 05/202 RECORD CHANGES APPROVED BY DATE

07/202 PROVED: MARK RUEBEL, P.E. NOJECT ANAGER: LINDA BARTOLINI VENEGAS 07/2022 07/2022 COLOGIST: ALEX LINCOLN 07/202 FSIGNER: MARK BEGGS, P.E 07/202 DARIAN KIS-YOUNG, E.I.T. 07/2022 CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.





King County Department of Natural Re


ources and Parks Water and Land Resources Division

River and Floodplain Christie True, Director

**BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4** 

**LEGEND AND ABBREVIATIONS** NOT FOR CONSTRUCTION


SHEET 2 OF 14 SHEETS



#### **CONSTRUCTION SEQUENCE NOTES:**

- 1. SCHEDULE AND ATTEND PRE-CONSTRUCTION MEETING AND NOTIFY PERMIT AUTHORITIES BEFORE STARTING CONSTRUCTION.
- 2. IMPLEMENT THE TRAFFIC CONTROL PLAN. SEE THIS SHEET.
- 3. IMPLEMENT THE TESC AND WATER MANAGEMENT PLAN. SEE SHEET 5.
- 4. PROTECT TRAIL DURING CONSTRUCTION AND REPAIR TO PRE-PROJECT CONDITIONS IF DAMAGED.
- 5. REMOVE (GRUB) INVASIVE VEGETATION AND DISPOSE.
- 6. REMOVE AND SALVAGE RIPRAP FROM LEVEE FACE.
- 7. COMPLETE LEVEE FACE ROCK REPAIR.
- 8. COMPLETE ELJ REPAIRS.
- 9. COMPLETE WETLAND ENHANCEMENT ELEMENTS.
- 10. FINISH UPPER BANK INSTALLATION OF COIR LIFTS AND NATIVE PLANTINGS.
- 11. REASSEMBLE, REPAIR OR RESTORE TRAIL TO PRE-PROJECT CONDITIONS.
- 12. RESTORE PUBLIC ACCESS TO TRAIL AFTER FINAL WALK THROUGH WITH PROJECT REPRESENTATIVE.
- 13. FOLLOWING CONSTRUCTION, REMOVE HIGH VISIBILITY FENCE AND REMOVE TESC FEATURES.
- 14. COMPLETE PLANTING PLAN PER SHEET 13.

#### **ACCESS AND TRAFFIC CONTROL NOTES:**



- 1. HEAVY TRUCK AND EQUIPMENT ACCESS AND EGRESS TO SITE IS ONLY VIA SR 169 (RENTON MAPLE VALLEY RD SE).
- 2. SECURE SITE EACH EVENING AND ON WEEKENDS WITH HIGH VISIBILITY FENCE OR EQUIVALENT.
- 3. OPEN TRAIL ON WEEKENDS AND HOLIDAYS.
- 4. PROTECT TRAIL WITH ROAD PLATES OR ADDITIONAL MEASURES.
- 5. TEMPORARY STAGING AREA SHALL BE FLAGGED BY THE CONTRACTOR AND APPROVED BY PROJECT REPRESENTATIVE PRIOR TO ANY CLEARING OR USE.
- 6. STREET SWEEP OR POWER BROOM ANY TRACK OUT ON CEDAR RIVER TRAIL AND MAPLE VALLEY RD SE IMMEDIATELY OR AS DIRECTED BY THE PROJECT REPRESENTATIVE.
- 7. TRAFFIC CONTROL SIGNAGE SIZE AND PLACEMENT SHALL BE INSTALLED IN COMPLIANCE WITH MUTCD ADOPTED BY WAC 468-95, IT'S MODIFICATIONS AND WSDOT SIGN FABRICATION MANUAL.
- 8. CONTRACTOR SHALL NOTIFY WSDOT TEN DAYS PRIOR TO SIGN INSTALLATION.
- 9. AFTER CONSTRUCTION REPAIR TRAIL TO PREPROJECT CONDITIONS OR BETTER.



Know what's below.

Call before you dig.

(UNDERGROUND UTILITY LOCATIONS ARE APPROX

		NUM.	REVISION	I BI	DAIL	
			TOICN			] ^
FIELD BOOK: DS/BM	05/2021		ON DESIGN			ŀ
SURVEYED: DS/BM	05/2021		30% DAFT	+		М
SURVEY BASE MAP: STH	05/2021		DRAI			] E
SURVET BASE MAP: STH	03/2021		~719022			ı
CHECKED: KLA	05/2021	$\vdash$	0/1202	+		DI
		NUM.	RECORD CHANGES APPROVED	BY	DATE	1
						Ļ

APPROVED: MARK RUEBEL, P.E. 07/2022
PROJECT MANAGER: LINDA BARTOLINI VENEGAS 07/2022
ECOLOGIST: ALEX LINCOLN 07/2022
DESIGNER: MARK BEGGS, P.E. 07/2022
DARIAN KIS-YOUNG, E.I.T. 07/2022
CAD DESIGN: DARIAN KIS-YOUNG, E.I.T. 07/2022

TARES OF TOWAL TO STORY OF THE PARTY OF TOWAL TO STORY OF THE PARTY OF TOWAL TO STORY OF THE PARTY OF THE PAR

1139129

ROJECT No



# King County

Christie True, Director

Department of Natural Resources and Parks Water and Land Resources Division River and Floodplain


#### BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4


ACCESS AND TRAFFIC CONTROL NOT FOR CONSTRUCTION


3 0F 14


SHEETS


RAFFIC CONTROL














SECTION 1+30 ROCK BARB

1:5

B
7

100 YR EL = 208.8 OHW EL = 203



Know what's below.


Call before you dig.

(underground utility locations are approx


			TOICN			APPROVED: MARK RUEBEL,
FIELD BOOK: DS/BM	05/2021		DESIGN			PROJECT
		1	30% 00-			MANAGER: LINDA BARTOLINI
SURVEYED: DS/BM	05/2021		DRAFI			
CURVEY DAGE MAD CTU	05/2021		Driving			ECOLOGIST: ALEX LINCOLN
SURVEY BASE MAP: <u>STH</u>	03/2021	1	1002%	1		·
CHECKED: KLA	05/2021		0/12022			DESIGNER: MARK BEGGS, P.
CHECKED: KLA	00/2021	1	J	1		
		NUM.	RECORD CHANGES APPROVED	BY	DATE	DARIAN KIS-YOUN
						DADIAN KIC YO

REVISION

E	APPROVED: MARK RUEBEL, P.E.	07/2022	
	PROJECT MANAGER: LINDA BARTOLINI VENEGAS	07/2022	
		07/2022	PR
	DESIGNER: MARK BEGGS, P.E.	07/2022	co
E	DARIAN KIS-YOUNG, E.I.T.	07/2022	
	CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.	07/2022	



1139129



# King County Department of Natural Reso

Department of Natural Resources and Parks Water and Land Resources Division River and Floodplain

River and Floodplain Management Section Christie True, Director BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4

**CONSTRUCTION NOTES:** 

EXCAVATION WITHIN 4 FEET.


1. FIELD VERIFY LOCATION OF VERIZON FIBER OPTIC LINE IF


2. PLACEMENT OF LARGE WOOD ELEMENTS MAY REQUIRE ADJUSTMENT OF EXISTING ROCK BARB

PROPOSED DESIGN - SECTION VIEW NOT FOR CONSTRUCTION

SHEET **8** OF

14 SHEETS








Know what's below. Call before you dig. (UNDERGROUND UTILITY LOCATIONS ARE APPROX.

			-01CN			] ^
FIELD BOOK: DS/BM	05/2021		ON DESIGN			lp
	05 /0004	lacksquare	30%			М
SURVEYED: DS/BM	05/2021	lacksquare	DRAFI			1
SURVEY BASE MAP: STH	05/2021		<u> </u>			Ð
SURVEY BASE MAP: STH	03/2021		~~10022			ı
CHECKED: KLA	05/2021		0/1202-			D
CHECKED: KLA	03/2021		<b>V</b> ·			
		NUM.	RECORD CHANGES APPROVED	BY	DATE	1
						1
						0

APPROVED: MARK RUEBEL, P.E.	07/2022	
PROJECT MANAGER: LINDA BARTOLINI VENEGAS	07/2022	
ECOLOGIST: ALEX LINCOLN	07/2022	PF
DESIGNER: MARK BEGGS, P.E.	07/2022	c
DARIAN KIS-YOUNG, E.I.T.	07/2022	
CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.	07/2022	
0.10 020.0.11		

1139129




Christie True, Director


King County
Department of Natural Resources and Parks
Water and Land Resources Division River and Floodplain

#### **BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4**

PROPOSED DESIGN - SECTION VIEW 2 NOT FOR CONSTRUCTION

SHEET 9 OF 14 SHEETS





KEY LOG SCHEDULE (BANK DEFLECTION JAM)

			· · · · · · · · · · · · · · · · · · ·	
LOG TYPE	COUNT	DBH DIA (IN)	LENGTH (FT)*	ROOTWAD
R4	3	24	40	YES
R5	1	24	35	YES
R6	4	24	30	YES
R7	1	24	25	YES
L2	1	30	45	NO
L3	4	30	30	NO
L4	1	24	40	NO
L5	2	24	35	NO
L6	2	24	30	NO
L7	1	24	25	NO

LOGS MAY BE FIELD FIT TRIMMED AS APPROVED BY PROJECT REPRESENTATIVE

APPROXIMATELY 50-60 RACKING LOGS AND 60-90 CY OF

#### 5.5 TON BALLAST BOULDER SCHEDULE (PER BDJ)

LAYER	COUNT	
1	6	
2	4	
4	14	
5	8	
TOTAL	32	

#### **ELJ CONSTRUCTION NOTES:**

- 1.GENERAL STRUCTURE LOCATION AND ORIENTATION SHALL BE STAKED BY THE CONTRACTOR PRIOR TO EXCAVATION. STRUCTURE LOCATION TO BE FIELD VERIFIED BY THE PROJECT REPRESENTATIVE FOLLOWING CONTRACTOR STAKING.
- 2.CLEAR AND GRUB AND ACCESS PRIOR TO ELJ INSTALLATION. ADJUST TEMPORARY WATER ISOLATION SYSTEM AS NECESSARY TO ENSURE WATER QUALITY REQUIREMENTS ARE MET.
- 3.ALL CONTROL POINT LOCATIONS SHALL BE STAKED BY THE CONTRACTOR AND APPROVED BY THE PROJECT REPRESENTATIVE PRIOR TO INSTALLATION.
- 4.PRIOR TO PLACING ANY ROCK OR LOGS, THE CONTRACTOR SHALL OBTAIN INSPECTION APPROVAL FROM THE PROJECT REPRESENTATIVE VERIFYING EXTENTS OF THE ELJ. IT IS THE CONTRACTORS RESPONSIBILITY TO NOTIFY THE PROJECT REPRESENTATIVE FOR THE INSPECTION. THE CONTRACTOR SHALL ALLOW 2 WORKING DAYS FOR THE INSPECTION TO TAKE
- 5.LOG MATERIALS SHALL BE PLACED AT THE LOCATION AND ORIENTATIONS SPECIFIED ON THE DRAWINGS OR AS DIRECTED BY THE PROJECT REPRESENTATIVE. TRIM CUT ENDS OF HORIZONTAL KEY LOGS TO FIT AS REQUIRED.
- 6.PLACE RACKING LOGS ALONG FACE OF STRUCTURES. RACKING LOGS AND SLASH SHALL BE PLACED TO CREATE AN INTERLOCKING MATRIX OF LOGS SECURED BETWEEN HORIZONTAL KEY LOGS.
- 7.PLACE SLASH OVER AND BETWEEN KEY LOGS AS SHOWN ON SHEET 11 FOR EACH LAYER SPECIFIED FOLLOWING PLACEMENT OF KEY LOGS AND RACKING LOGS.



Know what's below. Call before you dig. (UNDERGROUND UTILITY LOCATIONS ARE APPROX

30% DESIGN FIELD BOOK: DS/BM DRAFT SURVEYED: DS/BM 05/202 07/2022 SURVEY BASE MAP: STH 05/202 05/202 CHECKED: KLA RECORD CHANGES APPROVED

LAYER 4

BUMPER LOGS

FLOW

BANK DEFLECTION JAM SEQUENCE

07/202 PROVED: MARK RUEBEL, P.E. ROJECT ANAGER: LINDA BARTOLINI VENEGAS 07/2022 07/2022 COLOGIST: ALEX LINCOLN 07/202 ESIGNER: MARK BEGGS, P.E 07/202 DARIAN KIS-YOUNG, E.I.T. 07/2022 CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.

BUMPER

LAYER 5

STRUCTURE

1139129

FLOW



# **King County**


Department of Natural Resources and Parks Water and Land Resources Division River and Floodplain

Christie True, Director

**BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4** 


**ENGINEERED LOG JAM - SEQUENCE** NOT FOR CONSTRUCTION

SHEET 11 OF 14 SHEETS



#### **CONNECTION NOTES:**

- 1.BALLAST BOULDERS TO KEY LOG CONNECTIONS AND LOG-LOG CONNECTIONS MADE WITH CHAIN AS SHOWN ON DETAIL AND LAYER PLAN OR AS DIRECTED BY THE PROJECT REPRESENTATIVE. CHAIN LASHING SYSTEM SHALL BE PUT IN TENSION AND BE MAINTAINED DURING CHAIN SHACKLING.
- 2.CONNECT KEY LOGS TO STEEL PILES WITH CHAIN AS SHOWN ON DETAIL AND LAYER PLAN OR AS DIRECTED BY THE PROJECT REPRESENTATIVE.
- 3.CHAIN LENGTH NEEDED PER LASHING WILL VARY BASED ON DIAMETER OF LOGS AND LOCATIONS OF THE LASHING.
- 4.BALLAST BOULDERS REST ON THE ELJ LAYERS PREVIOUSLY CONSTRUCTED. BALLAST BOULDERS TO BE FIT AS CLOSE TO EACH LOG AS POSSIBLE, NO SLACK IN CHAIN UNLESS OTHERWISE NOTED.
- 5.CHAIN FOR LASHINGS SHALL BE  $\frac{1}{2}$  INCH DIAMETER GRADE 80 CHAIN.
- 6.ALL HARDWARE USED FOR LASHING AND CONNECTION SHALL BE OF THE QUANTITY AND TYPE SPECIFIED BY THE MANUFACTURER WITH AN EQUAL OR GREATER STRENGTH THAN THE CHAIN WORKING LOAD LIMIT OR AS APPROVED BY THE PROJECT REPRESENTATIVE.
- 7.MAR, PEEN OR ROUND ALL EXPOSED HARDWARE NUTS AND BOLT THREADS AFTER INSTALLATION FOR THEFT PROTECTION. PROJECT REPRESENTATIVE SHALL APPROVE ANY COATING PRIOR TO CONTRACTOR APPLYING IT. SECURE CHAIN TO LOGS USING 6 INCH LOGGING STAPLE.
- 8.CONTRACTOR MAY SUBMIT ALTERNATIVE CHAIN CONNECTION SYSTEM FOR APPROVAL




#### KEY LOG SCHEDULE (BANK DEFLECTION JAM)


LOG TYPE	COUNT	DBH DIA (IN)	LENGTH (FT)*	ROOTWAD
R1	1	18	15	YES
R2	2	18	20	YES

LOGS MAY BE FIELD FIT TRIMMED AS APPROVED BY PROJECT REPRESENTATIVE


# 5.5 TON BALLAST BOULDER SCHEDULE (PER LARGE WOOD ELEMENT)


LAYER	COUNT
4	1
5	2
TOTAL	3












SIMPLE LASHING LOG-LOG CONNECTION





BANK ROUGHENING STRUCTURE

KEY LOG SCHEDULE (BANK ROUGHENING STRUCTURE)

LOG TYPE	COUNT	DBH DIA (IN)	LENGTH (FT)*	ROOTWAD
R4	1	24	40	YES
R8	5	24	20	YES

5.5 TON BALLAST BOULDER SCHEDULE (BANK ROUGHENING STRUCTURE)

LAYER	COUNT
2	5
TOTAL	5



Know what's below. Call before you dig. (UNDERGROUND UTILITY LOCATIONS ARE APPROX

		NUM.	REVISION	BY	DATE	
			-0/CN			AF
FIELD BOOK: DS/BM	05/2021		20% DESIGIT			PF
SURVEYED: DS/BM	05/2021		30%	-		M/
SURVEYED: DS/BM	05/2021	ـــــ	DRAFI	-		4
SURVEY BASE MAP: STH	05/2021		DIV-	-		EC
OOKUE! BAGE WAY : OH!	00/2021	<u> </u>	07/2024	-		┨
CHECKED: KLA	05/2021	┢	0//20	-		DE
		NUM.	RECORD CHANGES APPROVED	BY	DATE	1
						l c

APPROVED: MARK RUEBEL, P.E.	07/2022	
PROJECT MANAGER: LINDA BARTOLINI VENEGAS	07/2022	
ECOLOGIST: ALEX LINCOLN		PROJECT No
DESIGNER: MARK BEGGS, P.E.	07/2022	CONTRACT No
DARIAN KIS-YOUNG, E.I.T.	07/2022	00111110111101
CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.	07/2022	

39129	
	10.3
	SIONA



## King County


ources and Parks Water and Land Resources Division

River and Floodplain Christie True, Director

#### **BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4**

**ENGINEERED LOG JAM - DETAILS AND NOTES** NOT FOR CONSTRUCTION

12 OF 14 SHEETS



#### **GENERAL PLANTING NOTES:**

- ALL PLANTS SHALL BE KEPT SHADED AND ROOTS MOIST UNTIL TIME OF PLANTING.
- PLANTING AREA BELOW THE COIR BLANKET TO BE COVERED WITH 3" LAYER OF ARBOR WOOD CHIP MULCH PRIOR TO PLANTING.
- WHEN INSTALLING TREES AND SHRUBS, PULL ARBOR WOOD CHIP MULCH LAYER BACK BEFORE DIGGING PLANTING HOLE.
- 4. NO SHRUBS SHALL BE PLANTED WITHIN 2' FROM EDGE OF PAVED TRAIL.
- 5. SETBACK TREES 4' AWAY FROM EDGE OF PAVED TRAIL.
- 6. PLANT SHRUBS 4' ON CENTER WITH 3' SETBACK FROM TREES.
- PLANT TREES 8-10' ON CENTER AND SETBACK 3' AWAY FROM SHRUBS.
- 8. PLANT ALL TREES AND SHRUBS IN SINGLE—SPECIES CLUSTERS THROUGHOUT THE PLANTING AREA. CLUSTERS = 2 TO 3 PLANTS.
- 9. KC ECOLOGIST SHALL APPROVE PLANT LAYOUT PRIOR TO PLANT INSTALLATION.
- 10. WATER ALL PLANTING AREAS IMMEDIATELY AFTER PLANTING. WATERING SHALL OCCUR AFTER THE INSTALLATION OF PLANT MATERIAL.
- 11. AFTER PLANT INSTALLATION, REPLACE ARBOR WOOD CHIP MULCH BY TAPERING IT DOWN TOWARDS THE STEM. KEEP ARBOR WOOD CHIP MULCH 2" AWAY FROM TRUNK OR STEM.
- 12. MAINTAIN TREE PROTECTION FOR ALL EXISTING TREES IN PROJECT SITE AND STAGING/ACCESS AREA UNTIL PLANTING IS COMPLETE.

			•	PLANT SCHEDULE			
SCIENTIFIC NAME	COMMON NAME	WETLAND INDICATOR STATUS	STOCK TYPE	SPACING ON CENTER (FEET)	PLANTING QUANTITY UPLAND PLANTING AREA TOTAL AREA = 4070 SF	PLANTING QUANTITY WETLAND ENHACENMENT TOTAL AREA = 3130 SF	LIVE STAKES IN COIR LIFT TOTAL AREA = 290 SF
rees	-	-		<u>'</u>			
	WSTN RED CEDAR	FAC	NO. 1 CON	12	10	5	
	DOUGLAS FIR	FACU	NO. 1 CON	12	10		
	BIG LEAF MAPLE	FACW	NO. 1 CON	12	10		
	SITKA SPRUCE	FAC	NO. 1 CON	12		5	
	COTTONWOOD	FAC	NO. 1 CON	12		10	
						TOTAL = 50 TREES	
rubs	•						
	Beaked Hazelnut	FACU	NO. 1 CON	5	24		
	Oceanspray	FACU	NO. 1 CON	5	24		
	Osoberry	FACU	NO. 1 CON	5	24		
	Serviceberry	FACU	NO. 1 CON	5	24		
	Snowberry	FACU	NO. 1 CON	5	24		
	Thimbleberry	FACU	NO. 1 CON	5	24		
	Pacific Ninebark	FACW	NO. 1 CON	5		10	
	Red Osier Dogwood	FACW	NO. 1 CON	2		80	
	Slough sedge	OBL	10" PLUG	0.5		80	
	Pacific rush	FACW	10" PLUG	2		40	
	LADY FERN	FAC	NO. 1 CON	2		80	
					TOTAL	= 434 Shrubs	
ve Stakes							
alix lasiandra	Pacific willow	FACW	LS	1.5		160	65
alix scouleriana	SITKA WILLOW	FACW	LS	1.5		80	65
ılix sitchensis	Scouler's willow	FACW	LS	1.5			65
ve stake basal diameter shall	be $\frac{3}{4}$ inch. LS means live stake, 6	feet long for coir lifts and 3 fe	eet lona for wetland en	hancement.			TOTAL = 435 Live Stake



Know what's below.

Call before you dig.

(UNDERGROUND UTILITY LOCATIONS ARE APPROX

07/2022 WWW.D

FIELD BOOK: DS/BM 05/2021

SURVEYED: DS/BM 05/2021

SURVEY BASE MAP: STH 05/2021

CHECKED: KLA 05/2021

NUM. RECORD CHANGES APPROVED BY DATE

 APPROVED: MARK RUEBEL, P.E.
 07/2022

 PROJECT
 07/2022

 MANAGER: LINDA BARTOLINI VENEGAS
 07/2022

 ECOLOGIST: ALEX LINCOLN
 07/2022

 DESIGNER: MARK BEGGS, P.E.
 07/2022

 DARIAN KIS-YOUNG, E.I.T.
 07/2022

 CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.
 07/2022



1139129

Department of Natural Resources and Parks Water and Land Resources Division River and Floodplain Management Section

Christie True, Director

BELMONDO LEVEE REPAIR CEDAR RIVER RM 10.4

PLANTING PLAN
NOT FOR CONSTRUCTION


SHEET

13

OF

14

SHEETS



### TYPICAL LIVE STAKE PLANTING DETAIL

SLOPE SURFACE SHALL BE SMOOTH BEFORE PLACEMENT FOR PROPER SOIL CONTACT STAKE PATTERN AS PER MANUFACTURER'S RECOMMENDATIONS. IF THERE IS A BERM AT THE TOP OF THE SLOPE, ANCHOR UPSLOPE OF THE BERM MIN. 4" OVERLAP ANCHOR IN 6"x6" MIN. TRENCH AND STAKE AT INTERVALS PER MANUFACTURERS DIRECTIONS WITH 2"x2"x18" WOOD STAKES OVERLAP STAKE OVERLAPS MAX. 2' SPACING ANCHOR IN 6"X6" MIN. TRENCH AND STAKE AT INTERVALS PER MANUFACTURERS DO NOT STRETCH EROSION CONTROL BLANKET TIGHT -DIRECTIONS WITH 2"X2"X18" WOOD STAKES ALLOW THE ROLLS TO MOLD TO ANY IRREGULARITIES SHINGLE OVERLAPPING BLANKETS FOR FLOW IN DOWNSTREAM DIRECTION.

WHEN THE PLANTING HOLE HAS BEEN BACKFILLED, POUR WATER AROUND THE ROOTBALL TO SETTLE THE SOIL. ROUND-TOPPED SOIL BERM -- ENSURE ENTIRE PLANTING AREA IS DECOMPACTED PRIOR TO ARBOR WOOD CHIP MULCH PLACEMENT. 4" HIGH x 8" WIDE ABOVE ROOTBALL SURFACE SHALL BE CONSTRUCTED AROUND THE ROOTBALL. BERM SHALL BEGIN AT ROOTBALL 3" LAYER OF ARBOR WOOD CHIP MULCH - FINISHED GRADE - EXISTING SOIL PLANT AT THE ROOT FLARE. - 2" CLEAR ZONE AROUND PLANT STEM BOTTOM OF ROOTBALL — RESTS ON EXISTING OR RECOMPACTED SOIL. \_3x WIDEST DIMENSION OF ROOTBALL

- SHRUB

PLANTING OF SHRUBS, TREES, ETC. SHOULD OCCUR SMALL TREE, SHRUB AND GROUND COVER PLANTING

1139129

#### EROSION CONTROL BLANKET (ECB)

SEED, FERTILIZE, AND MULCH BEFORE MATTING INSTALLATION.



Know what's below. Call before you dig. (UNDERGROUND UTILITY LOCATIONS ARE APPROX

		NUM.	REVISION	I BI	DAIL	
						Αł
FIELD BOOK: DS/BM	05/2021		20% DESIGN			PF
	-		30%			I м
SURVEYED: DS/BM	05/2021		CD/T			l ''''
CURVEY BASE AND CTU	05 /0004					<b>1</b> EC
SURVEY BASE MAP: <u>STH</u>	05/2021		10027			
CHECKED: KLA	05/2021		07/2022			DE
CHECKED: KLA	03/2021	ł	<b>Q</b>	1		ı
		NUM.	RECORD CHANGES APPROVED	BY	DATE	J
						l
						C/

	APPROVED: MARK RUEBEL, P.E.	07/2022	
	PROJECT MANAGER: LINDA BARTOLINI VENEGAS	07/2022	
	ECOLOGIST: ALEX LINCOLN	07/2022	PRO
	DESIGNER: MARK BEGGS, P.E.	07/2022	CON
4	DARIAN KIS-YOUNG, E.I.T.	07/2022	
	CAD DESIGN: DARIAN KIS-YOUNG, E.I.T.	07/2022	



# **King County**

Department of Natural Resources and Parks Water and Land Resources Division

TOP OF ROOT BALL SHALL BE FLUSH

WITH FINISHED GRADE.

River and Floodplain Christie True, Director

<b>BELMONDO LEVEE REPAIR</b>
CEDAR RIVER RM 10.4

**PLANTING PLAN DETAILS** NOT FOR CONSTRUCTION

SHEET 14 OF 14 SHEETS