## Life Cycle Cost Analysis (LCCA)

### First NE Transfer/Recycling Transfer Station Shoreline, WA

, February 15, 2006

Lisa Williams, Solid Waste Division Patrick Domres, Solid Waste Division

#### King County Building Summit: Dollars and Sense Tools to Green Your Project



## Overview

### Background

- Budget: \$30M (incl. design & construction)
- Scope of Work: New Transfer/Recycling Station
- Schedule: Begin Construction Summer 2006 (18-months)

Ist LEED<sup>™</sup> Certification Building that is a Transfer Station

Goal: Silver Certification, will try for Gold

□Focus on Major LEED<sup>™</sup> Components

## Overview

 Incorporate as much LEED<sup>™</sup> components during the design phase.

Did not go over budget, the Design Team found ways to work smarter!

What you can take away from this workshop.

#### First NE Transfer / Recycling Station (Existing Site Plan)




#### First NE Transfer / Recycling Station (Southeast View)



#### First NE T/R Station Interior View (looking south)



#### First NE Transfer / Recycling Station Interior View (North)



### The Process for Designing a Green Building

Eco Charrette

- □ Sets the stage of the leed project, helps educate Team
- Goal: what ways to maximize the greatest impact

DESIGN PHASE

Implement results from Eco Charrette in the Specifications

Perform studies on the energy, water, and ventilation systems

#### CONSTRUCTION

- □ A lot of contractors are not aware of LEED<sup>™</sup>
- Design Team coordinates with and educates the Contractors i.e. use low voc ---install carpart after walls have been painted.
- COMMISSIONING
  - □ Process required by LEED<sup>™</sup> that includes, but not limited to all the building systems are tested by an independent consultant

SZ -

BUDGET (With LEED<sup>™</sup> versus Without LEED<sup>™</sup> products)
 □ Figures are compared during the Design Phase

# LEED<sup>TM</sup> COMPONENTS

- Water Harvesting Tank
- Daylighting
- Solar Photovoltaic
- Alternative Fuel
- Indoor Environmental Quality

Outdoor Elements

SWDI WPD0206

## Water Harvesting Tank

 Collects rainwater from roof (42K SF) and uses it to wash down transfer station floor and supplies water to the public restrooms.


Saves funds by "Cost Shifting"

- i.e. -- reduces water bill
  - -- combines downspouts into one pipe.


Saves approx. 254,000 gallons/year or 57%

- Harvesting Tank stores 3,700 gallons.
- 1/10 inch of rain fills the tank

### Water Harvesting Tank (Diagram)



### **Daylighting Design**



# Daylighting

- Panels absorbs sunlight and illuminates transfer station.
- Study based on Cloudy Day.
- Panels are translucent and produces a soft light.
- Never falls below the LEED<sup>™</sup> Level.
- Scheme A, B, C (A- Not enough light, B & C- Meets SWD standards).
- Photo cell senses daylight and automatically dims station lights.

- Reduces energy usage.
- Saves funds by: combining the panels and ventilation system into one unit.
  - ---- Saves approx. 89% per/year light bill
- Pays for itself with approx. 3 years.

# Solar Photovoltaic

- Panels located on the southside of the building's roof.
- Absorbs sunlight and converts it to energy.
- Visible feature.
- Cost of the panels would not pay for itself.
  Looked for other funding sources.
- Applied for a grant with the City of Seattle
- Grant requires SWD to educate public about the solar panels i.e. Kiosks, tours
- Projected to provide a savings of 5% of the buildings energy cost

## **Alternative Fuel**

- 5% Bio diesel
- Standard policy by SWD
- LEED<sup>TM</sup> will recognize alternative fuel as either one of the following:
  - --- Alternative to Credit SS 4.3

(Sustainable Site 4.3 – Alternative Transportation/Fuel Vehicles)

--- An "innovation in design" credit

- Creative thought process
- Integrate into project

# Indoor Environmental Quality


- Carbon Monoxide Monitoring on tipping floor
  - No credit
  - □ Right thing "to do"
  - Health of the Operator
- Carbon Dioxide Monitoring within Operators office
- No Smoking Policy (incl. in the specs)
  - During construction, Contractor will be required to smoke in "smoking only" designate areas.
  - SWD Staff will be only allowed to smoke in Smoking Designated Areas outside of the new building
- Low Emitting Materials Carpet, Paints, Adhesives
- Pushes LEED<sup>TM</sup> Envelope

# Increase Ventilation Effectiveness

- Saves 50% of Fan Energy
- Passive system is more effective than mechanical fans
- Mechanical Design: produces 5 Air Changes per Hour (ACPH)
- Building Design (with no power): produces 6 ACPH
- Cross Ventilation: 8 ACPH
- SW wind 11 month
- NW wind 1 month
- Average nominal wind speed at 30 feet above ground surface is 7 MPH

## **Natural Ventilation**

#### Natural Ventilation - Cross



## **Outdoor Elements**

- Design revolves around Thornton Creek
- Demonstrate 3<sup>rd</sup> party commitment
- Call on community
- Received Community Award from Thornton Creek Alliance
- Native Plants used

• 75' Buffer

- No irrigation system installed; saves on water
- Water Efficient Landscaping
- Storm Drainage Vault with special filters
- Runoff from roadway → Filter → Pond → Released to the Thornton Creek at a rate that will enhance the ecology instead of hurt it.
- Bio Swale –natural system has plants and grasses.

# LEED PAYBACK?

### Hard Cost

- 57% water savings
  - 89% light savings
  - 50% fan energy via natural ventilation

### Soft Cost

- Thornton Creek Community
- Great PR for SWD
- Employee Production increases

# QUESTIONS ?

Thank you!

Lisa Williams, Solid Waste Div Patrick Domres, Solid Waste Div

