

Ravenna Creek pipe extension

Completed - Fall 2011

This project was completed in three phases from May 2008 to September 2011.

Phase A was implemented in May 2008 and continued until mid-2010. This phase implemented aggressive cleanup measures after an accidental wastewater release into University Slough was discovered on May 23, 2008. Restoration of the cleanup area was coordinated with University of Washington staff.

Learn more: King County response to Ravenna Creek Sewer spill, May 2008 $\ \square$

Phase B of the project took place during Summer 2010.

This phase consisted of extending the pipeline that conveys Ravenna Creek downstream from Ravenna Park. A section of pipeline was added to isolate the stream and prevent potential sewer overflows into University Slough.

Learn more: construction begins Monday August 23, 2010. Ravenna Park Ball Field, adjacent trails closed to public through October \square , Aug. 19, 2010

Phase C of the project was constructed in September of **2011.** This phase involves the installation of three large logs with root wads (called "large woody debris" or "LWD") in University Slough as mitigation for the temporary rerouting of Ravenna Creek flow to the combined sewer system instead of University Slough during Phases A and B of the project. Placement of LWD in the slough will create fish habitat and promote biological diversity. The LWD consists of three cedar or fir logs with root wads that are placed in the slough and its buffer as shown on the attached site plan. Each of the logs would be approximately 20 ft long and approximately 16 to 20 inches in diameter at breast height. The bank-side end of each log would be embedded in the ground and anchors would be used to permanently secure the logs in place. The construction area would be dewatered during construction to facilitate installation of the LWD and minimize construction impacts to slough water quality and fish. Dewatering would be accomplished by placing temporary sandbag isolation dams in the slough and pumping slough water around and out of

You can download and view documents (PDF files) using a <u>PDF Reader</u>.

Library

the construction area.

Updates and presentations


 University Slough Wastewater Overflow Mitigation Project. A State Environmental Policy Act (SEPA) Determination of Nonsignificance (DNS) was issued on March 14, 2011, for University Slough



Figure 1. Site plan. University Slough Wastewater Overflow Mitigation Project – Phase C. Source: <u>SEPA DNS and environmental checklist</u> , March 14, 2011.



Project location map [



New box culvert with pipe extension □

mitigation work proposed for Summer 2011. View the SEPA DNS and environmental checklist.

- <u>Invasive species removal in Ravenna Park begins</u>
 <u>Thursday August 26, 2010</u>. Aug. 24, 2010
- Construction begins Monday August 23, 2010. Ravenna Park Ball Field, adjacent trails closed to public through October. Aug. 19, 2010
- Ravenna Creek pipeline construction begins August 2010, July 2010
- Ravenna Creek Transfer Pipe Extension Project scheduled to begin June 2010, Mar. 16, 2010
- Presentation: <u>Ravenna Creek Transfer Pipe Extension</u> <u>Project</u>, Oct. 5, 2009
- <u>Ravenna Creek Transfer Pipe Extension Project</u> –
 <u>summary of communications, what we're hearing from the community</u>
 People concerned about Ravenna Park and Creek have

brought their questions, comments, and concerns to King County staff at a community meeting on September 10, 2009, in emails, and in phone calls. <u>Learn more</u> what people are saying and asking, and find the county's responses, where appropriate.

Summer 2009 project update

Ravenna Creek sewer	spill	<u>, May</u>	<i>/</i> 2008
---------------------	-------	--------------	---------------

- King County response to Ravenna Creek sewer spill,
 May 2008 □
- View \(\text{video of cleanup} \) (WindowsMedia)
- News Release, June 13, 2008 <u>University Slough south</u>
 of Clark Rd Bridge reopened to public after King County
 completes cleanup □

Wastewater Treatment Division

King Street Center 201 S. Jackson St., Suite 500 Seattle, WA 98104

Get directions

Contact us	Co	nta	ct	us
------------	----	-----	----	----

206-477-5371
WTD Division Directory
website.wtd@kingcounty.gov

Last Updated August 17, 2016