CSI Program Update: Status Briefing

May 5, 2016



Department of Natural Resources and Parks Wastewater Treatment Division



Presentation Topics

- Presentation Topics:
 - CSI Program Update status
 - Initial findings from development of conceptual projects to address identified conveyance system needs
 - Conceptual project examples
 - ESI considerations

Steps to Complete CSI Program Update



Initial Findings of CSI Conceptual Project Development

- Overall there are increases in peak flows from model basins between 2000 and 2010 generally due to:
 - <u>Data collection in 2000-01</u> was short duration (2, 6week periods) and a **dry** period resulting in model basin calibration based on lower measured flows.
 - <u>Data collection in 2009-11</u> was long duration (24 months) done during a **wet** period resulting in model basin calibration based on higher measured flows.
- Due to flow increases extrapolated 2060 peak flows (population growth and I/I degradation) vary and in some cases are larger than the predicted 2050 peak flow in 2007.

Initial Findings of CSI Conceptual Project Development

- Implications:
 - Use of storage
 - Size and duration of peak flows make storage a less likely option.
 - Large storage facilities are very expensive and in some cases not feasible to site.
 - Project costs have increased as compared to 2007 CSI Update
 - Due to impacts associated with long linear pipe parallel/replacement projects rather than small storage facilities.
 - A large capital project to increase capacity in Eastside Interceptor maybe needed

Auburn Interceptor Storage Curve



Medina Trunk Example

 2007 CSI Program Update
 70,000 gallon storage facility to meet 2050 - 20 year peak flow



- Site storage in street right of way
 Estimated
 - construction cost – \$0.5M (2006 \$)

Department of Natural Resources and Parks Wastewater Treatment Division

The information included on this map has been compiled from a variety of sources and is subject to change without rotes. If ing Courty missions representations or warranties, express or implied, as to assurancy, completeness, timeliness, or rights to the use of such consequential damages installing has not intrinsifio to incremes or to forgutis soulting from the use or misse of the information contained on this map. Any sale of this map or information on this map is prohibited except by without pervision of this [Courty,

FileName: Q:WTD/Projects/CSI_Project/Projects/200609ReportProjects/ProposedP Medina: storage.mxd-peter keymise Medina Storage

NE Lake Washington Planning Basin

Medina Trunk Example

2017 CSI Program Update 1.5 MG Storage Facility to meet 2060 - 20 year peak flow



Division

Planning Basin

- Updated estimated construction cost - \$12 M (2016\$)
- Recommended 0 new concept replacement of trunk estimated construction cost - \$4 M

South Lake Sammamish Planning Area Example

- > 2007 CSI Program Update
 - 6.7 MG of storage in 3 projects
 - 3.5 mile new pipe for diversion
 - Estimated construction cost \$42 M (2006\$)



South Lake Sammamish Planning Area Example

- 2017 CSI Program
 Update Storage
 Concept
 - Would now need
 28 MG of storage
 in 2 projects plus
 3.5 mile new pipe
 for diversion
 - Updated estimated construction cost \$156M



South Lake Sammamish Planning Area Example > 2017 CSI Program

- 2017 CSI Program
 Update Large
 Diversion and
 Storage
 - Recommend diversion with 7 miles of new pipe and new pump station estimated construction cost \$130M
 - Small storage in Issaquah TBD



Eastside Interceptor

- > 2007 CSI Update
 - Generally lower peak flows
 - Numerous storage projects upstream of ESI to attenuate flows.
 - Diversion at York
 Pump Station



Potential New ESI Capacity Project

Higher flows and replacing upstream storage projects with replacements/parallels may result in the need for a large ESI storage project.



Ongoing Conceptual Projects Work

- March-May: Develop conceptual projects to address all identified CSI capacity needs.
- May-July: Refine conceptual projects based on input from WTD workgroups (e.g. operations, asset management, etc.) and MWPAAC E&P.
- August-September: Finalize conceptual projects.
- October- December: Prioritize conceptual projects to address CSI needs and finalize CSI Program Update.



For additional information or questions, please contact:

Steve Tolzman, Project Manager CSI Program Update Wastewater Treatment Division 206.477.5459 Steve.Tolzman@kingcounty.gov